

WIND ENERGY CENTRE - OPEN HOUSE

Construction Plan

Turbine siting and surveys:

- ✦ Site preparation will include final turbine siting and surveys
- ✦ During these surveys, boundaries of turbine sites will be staked and existing buried infrastructure will be located and marked

Access roads:

- ✦ Municipal and Provincial roads will be used to transport equipment to the construction sites
- ✦ Minor modifications may be required to some of the existing roads (e.g. widening the turning radii) to transport equipment
- ✦ New access roads will typically be 10 m (34 feet) wide during the construction phase
- ✦ No permanent paved roads will need to be constructed for the turbines
- ✦ Equipment will be delivered by truck and trailer as needed throughout the construction phase and stored at temporary laydown sites surrounding each turbine

